

After Installation

Waste and Work site

- Sharp, metal off-cuts should be picked up and isolated as you work (they are a cutting hazard).
- Empty packaging should be disposed of to landfill.
- Plaster board and other off-cuts should be cleaned up and disposed of to landfill.
- Workplace will be cleaned and left free of debris or hazardous material.

Tools

All tools will be cleaned and stored in accordance with work site practice

Industry productivity guidelines:



This unit standard requires that your work must meet industry productivity guidelines, which set out the amount of work you are expected to be able to complete in a day.

You need to consistently construct:

- *15 linear metres (lm) of proprietary partitions per day for commercial environments;*
- *13 linear metres (lm) of proprietary partitions per day for multi-storey environments.;*
- *also:*

Task	Commercial environment	Multi-storey environment
Fabricate and fit openings in walls to receive glass	10 openings per day	6 openings per day
Fabricate and fit openings in walls to receive doors	10 openings per day	7 openings per day
Fit and hang doors with all hardware to the openings	4 per day	4 per day